Foxfab
POWER SOLUTIONS

PRODUCTION RELEASE FORM

GENERAL INFORMATION

Job No.:	J15353-03
Model No:	FFCC-C1-1200-V4-ALU-LA-AC-AF-2WSDS-AD2-AD3-AD5-AG-FUS
Catalog No:	FFCC-C1-1200-U4-G-ALU-LA-AC-AF-2WSDS-AD2-AD3-
Date:	7/15/2025
Job Name:	Batesville

ELECTRICAL RATING INFORMATION

Voltage:	480Y/277 VAC
Current:	1200A RMS
PH/W/Hz:	3PH/4W/60Hz
SCCR:	65kA RMS SYM.

SPECIFICATION/APPROVAL INFORMATION

ETL/CUL/UL SPEC:	ETL 1008
E File #:	4011005(ETL)
Drawing No:	FFCC-C1-1200-U4-G-ALU-LA-AC-AF-2WSDS-AD2
Drawn By:	BB
Approved By:	BB
File Compliance Mech:	GC
File Compliance Elec:	KB

DETAILED REQUIREMENTS

Camlock Configuration

M/F	M
Colours	U4 - BN/OR/YL/WH/GN
Qty (PH)	3
Qty (GND)	1
Lug Config	LA

Enclosure Information

Size	72 x 36 x 30
Material	5052 Aluminum
Rating	Type 3R
Colour	ASA 61 GREY
Qty	1

OPTIONAL ACCESSORIES

			Specification
(AA)	☐	Camlock Snap Covers	
(AC)	X	Heater with stat	250W
(AD)	X	Additional Outlets (Specify if GFCI)	20A GFCI Receptacle, 30A L5-30R Twist-Locking Receptacle, 50A 5-50 Receptacle, 1 EA
(AE)	☐	Key Interlock	
(AF)	X	Terminal Strip	
(AG)	X	Phase Sequence Relay	
(AH)	☐	Power Meter	
(AI)	☐	Micro-Switch	
(AJ)	☐	Leg Stand Kit	
	X	Tranformer required?	SP50ACP

EQUIPMENT SPECIFICATION

FFCC-X2 (T)	☐	Transfer switch	
FFCC-X2 (D)	☐	Disconnect Switch	
FFCC-X3	☐	Breaker(s)	
	☐	Other	

NOTES & COMMENTS

2WSDS- 2 Wire Source Destination Switch

3x 800A Class-L Power Fuses

ATTN Assembly: Please use a WDU 6 terminal block for the 50A Receptacle Neutral

Ground must be sized to 50% of current load (600A rated copper bus)

100% neutral needed